

Diagnoses the Causes of Cost Deviation in Iraqi Construction Projects

Eman A. Mahde*, Nidal A. Jasim

Department of Civil Engineering, University of Diyala, 32001 Diyala, Iraq

ARTICLE INFO

Article history:

Received 25 April 2021

Accepted 20 July 2021

Keywords:

Construction project; Cost deviation;
Root cause analysis; Fishbone Diagram;
Pareto Chart; 5- Why analysis;

ABSTRACT

There are challenges with cost deviation and time overruns in every project in the building sector, whether they're residential projects, infrastructure projects, or anything else. The study aims to find the most important causes of cost deviation in a construction project. The researcher depends on Root Cause Techniques. These techniques are a good choice for diagnosing the root causes of cost deviation in a construction project. Many roots cause analysis tools have emerged from the literature as generic standards for identifying root causes such as the Fishbone Diagram, Pareto Chart, and the Five-Why techniques. This study diagnosed nineteen causes of cost deviation in the selected project (Dar Al- Nahrain building), These causes can be classified into three categories (planning causes, designing causes, and execution causes). According to Pareto analysis, the most important reasons for cost deviation are 10 out of nineteen causes. According to the Pareto chart above, the designing causes group (C2) and the planning cause group (C1) are responsible for 80% of the problem. As a result, focusing on these two major causes will solve 80% of the problem's project deviation in building projects. The results were filtered using the 5-Why analysis, which concluded that the project's cost deviation was due to insufficient project information, which is the root cause for the planning causes group, unclear owner requirements for the designing causes group, and changes in orders for the execution causes group

1. Introduction

A construction project will be successful if its technical objectives are combined with its budget and if it is not exceeded, as a result, it is hard to imagine a building project being finished without cost variations and time overruns, which can occur at any step of the process, including design, planning, and execution, due to a range of variables such as bad management, control, and supervision. As a result, the main cause of cost variance is the application of traditional cost estimation methods or formulas. A list of problems appears during the selection of project criteria and their proper evaluation.: [1]and [2]:

1. The lack of modern and advanced means of estimating the project cost.

2. The lack of an integrated database for the project
3. Not using engineering alternatives in the planning, design, and implementation stages, and as a result of what was mentioned above, in addition to many reasons related to unstable construction conditions.

Most construction projects include a distinct set of tasks that must be completed in order to produce a distinct product. New buildings and structures, additions, adjustments, conversions, expansions, reconstruction, renovations, significant replacements, and mechanical and electrical installations are all examples of construction projects. Controlling costs and timeliness is critical in the construction business

* Corresponding author.

E-mail address: affulla770@gmail.com

DOI: 10.24237/djes.2021.14304

to ensure that projects are finished on time and on a budget [3].

Generally, the success of a construction project is judged by the project's capacity to meet the client's objectives for cost, schedule, safety, resource allocation, and quality. In (2001), Kagioglou, Cooper, and Aouad [4], confirm that a successful project is one that has met its technical objectives, stayed on schedule, and stayed within budgetary constraints. According to Rahman et al. (2012) support the idea that on-time and on-budget performance is the most important criterion for a project's success.

In (2010), Olawale and Sun [5], showing that the construction sector as a whole has been considered as having poor performance, which has resulted in an inability to achieve efficient cost performance. As a result, most construction projects confront significant cost variance.

In (2013), Ameh, Soyngbe, and Odusami [6], explain that the history of the construction business worldwide is littered with projects that were finished with large cost overruns.

In (2016), Faiq and Reem [2], follow up of cost control in Iraqi highway projects was investigated. The survey includes an examination and analysis of the reality of cost planning and control, as well as the causes of building cost deviations that arise over the course of work. Personal interviews and surveys were conducted with project manager, as well as a study of existing research, were used to investigate and collect data on the causes of cost deviation.

In Iraq, the construction sector encountered a number of challenges and issues that prevented project management approaches from being used in construction projects. In this study, the author attempted to employ a variety of novel methods for identifying problems and impediments in building projects before making ideas for a simple application for one of the project management approaches [7].

Because the scheduling of critical decisions can have a major impact on costs, it's important to identify elements that influence overall project costs early on. Based on an analysis of data from several projects, this report reveals major cost-influencing aspects. From planning

to operation, the database for that study contained information on project details, building specifications, dimensions, and costs at different phases of the project life cycle. [8].

In (2020), Mustafa, and Sedqi [9], explain that Many infrastructure projects suffering from corruption elements during the contractor selection phase. To diagnose the project cost deviation, root cause analysis methodologies such as Fishbone, Pareto chart, and Five-Why were utilized.

Based on a survey of the literature and some discussions with project managers, the research problems are stated as follows:

- A lack of documentation of past project cost records, as well as a lack of data on construction project management.
- Because of currently available techniques are ineffective and have various drawbacks, such as being outdated, old, slow, and uncertain, there is a defect in the cost estimation of construction projects. Aside from the need for modern, efficient cost estimating procedures that offer a variety of benefits such as being innovative, fast, efficient, flexible, and simple to use, there is also a demand for modern, efficient cost estimating approaches. As a result, as a modern method in the construction business, root cause analysis methodologies must be used to assure successful management.

Despite the necessity for public infrastructure construction projects in the current decade, projects are being awarded to project managers that lack the necessary information.

Significant research described as follows:

- The cost deviation for construction projects is highlighted in this study and find the correct ways to reduce this deviation.
- It gives project managers and planners a better understanding of the situation they face and how to overcome and remove them when using the cost management strategy for construction projects.

The study was restricted to the following parameters:

- Time limitations: data collection began in 2020.
- Spatial limits: This research focused on the Dar Al-Nahrain printing project in the Iraq Republic.
- To achieve the study's objective, research use a three-step methodology:
- The literature Review.
- Questionnaire survey and individual interviews with building project engineers with specialist knowledge, as described in reference [2]
- Using Statistical Analysis

Finally, the primary goals of this research are to identify and diagnose the reasons of cost variance in construction projects through multiple groups (the planning causes, design causes, and execution causes), and to quantify the relative importance “RI” of each cause., and finding out realistic solutions that reduce cost deviation the project.

2. Methodology

In this study, the researcher used statistical analysis and identified the most affecting factors on cost deviation of the project construction.

The first part of the questionnaire related to the personal information of the respondents about his scientific and expertise and the institution in which he works. Then,

Open the questionnaires are free-form survey questions that allow respondents to respond in open text style, allowing them to react based on their full knowledge and understanding. [10].

In the work sector, a questionnaire was distributed to specialized engineers and engineering experts in a construction project. level of percentage 100 percent is shown in Figure (1).




Figure 1. Work sector

The distribution of the research sample administrative level of Percentages 100 percent (50 total number) is shown in Figure (2).




Figure 2. Administrative level

Figure (3) shown years of experience and the distribution of the research sample's experience percentage (50 total number).



Figure 3. Years of experience

The researcher follows up the same procedure by Al- Zwainy and Neran [11], and Nidal [12] who they diagnosed the causes of projects deviation by selecting a number of factors that had been identified through previous studies and the sources that have been found, and accordingly, these interviews were

conducted for the purpose of taking the opinion of experts to know the extent of the importance of each factor on the construction project. Finally, A list of factors that influence the project's cost was prepared. The methodology can be summarized in Figure (4).




Figure 4. Research methodology

The second part of the questionnaire consists of nineteen causes, from this part, the researcher has identified the most influential factors on the selected project (Dar Al-Nahrain building) in Iraq, as shown in Table (1) and by using statistical analysis techniques, compute the weight of secondary causes, relative important index (RI %) and Rank.

After that, the reasons for the cost deviation were divided into three groups, which are in the planning, design, and implementation stage.

3. Concept of root cause analysis

The Root Cause Analysis (RCA) is a method that is used to address a problem or non-conformance, in order to get the “root cause” for the problem [13]. RCA is a popular technology and is often used to help people answer the why

question. RCA seeks to identify the origin of the problem by using a specific set of related steps in order to find the main cause of the problem. The works of this technique can be summarized as shown in Figure (5). This technology has the potential to be applicable not only to engineering but also to other disciplines [14]; [15]. This method can be used to resolve problems when the "root cause" of the issue cannot be reached. RCA is used to eliminate or mitigate the cause of the problem and prevent it

from repeating. RCA is simply a collection of well-known techniques that can be used to produce a structured, quantitative, and documented approach to defining, understanding, and resolving the fundamental causes of project cost deviation [14]. Root cause analysis is more than just a phrase; it is a formal and well-structured methodology that is used as part of a total quality management approach [16].




Figure 5. Workflow of RCA

4. Techniques of root cause analysis

Numerous tools are available for RCA techniques. Such as (Pareto Analysis, Causal Tree, Brainstorming, Nominal Group Technique, and Five-Why Analysis) are all examples of creative thinking. The researcher will concentrate on (Fishbone Diagrams, Pareto Diagrams and 5- Whys technique) in this study. The study included investigating, evaluating, controlling costs, and determining the causes that lead to cost deviation [17].

4.1 Fishbone diagram

These techniques are known as Ishikawa diagrams, cause and effect analysis, or "Fishbone Diagrams" because the final diagram resembles a fish's skeleton [14]. The cause and effect diagram are a method for examining the reasons for a problem in a systematic manner. This tool is often used after performing a Pareto analysis or brainstorming to arrange the resulting ideas [17]. This type of graph is used

to identify all the causes that contribute to the occurrence of the problem and thus find solutions

4.2 Pareto Chart

The Pareto principle, introduced in the 9th century by the Italian economist scientist Pareto, is used to focus on the most critical problems, Philfredo Barreto, which shows that a small number of factors causing the problem represent a large proportion of the total cases (such as complaints, defects, and problems), that is, the classification of cases according to the degree of importance and concentrate on resolving the most relevant problem while ignoring those of less importance [18].

4.3 Five- Why technique

It is one of many brainstorming approaches that involves continually asking "why" five times to assist find the fundamental reason of a problem. When a problem is repeatedly questioned, a new solution appears each time,

which is linked to the root cause. However, the question of why can be continued until an acceptable solution is found. The number five is chosen at random. The theory goes that if you question "why" five times, you'll eventually find the core cause [19].

5. Using “Root Causes”, to determine the cause of cost deviation in a construction project.

In order for the researcher to obtain the root causes that lead to cost deviation in construction

projects, The weight of each reason was calculated using a survey analysis method, and these reasons are very essential in root cause analysis.

In this paper, the researcher relied on a literature review, questionnaire, and personal interviews with experts. The causes of cost variance in the Dar Al- Nahrain building project have been determined for various categories (planning causes, designing causes, and executing causes). as it is shown in Table 1. below:

Table 1: Main and secondary causes of cost and schedule deviation

Main causes	Symbol	Secondary causes	Symbol
Planning causes	C1	Inflation or changes in the cost of raw material.	C11
		Deficiencies in general contractor’s organization	C12
		Poor contract administration	C13
		Insufficient information about the project	C14
		The implementation method is not appropriate with the project type	C15
		The contracting type's incompatibility with the project type	C16
Designing causes	C2	Owner requirements unclear	C21
		Design changes	C22
		Mistakes in design documents	C23
		Unrealistic tender cost estimation	C24
Execution causes	C3	Site incidents and delays due to lack of safety measures	C31
		Changes in orders	C32
		failure to agree and conflict management	C33
		Issues of imported materials and restrictions	C34
		The late delivery of materials and equipment	C35
		Frequent breakdowns of construction equipment	C36
		Lack in general employment	C37
		Lack of skilled labor	C38
		Project environment conditions	C39

5.1 Secondary planning causes analysis

The researcher found that the planning reasons (C1) consist of (6) causes which are arranged in “Table 1. and Table 2.” with mentioning the weights (note: the weights

represent the results of the field survey) in addition to the relative importance and arrangement of each factor within the planning group. Figure (6) and Figure (7) show the Fishbone diagram and Pareto diagram for planning causes.

Table 2: The Weights, Relative Important and Ranking for secondary planning causes

Main Causes	Secondary Causes	Weight of secondary causes	Relative important index RI (%)	Rank	
Planning reasons	C11	63.66	12.95	5	
	C1	C12	55.45	10.1	6
		C13	81.55	20.78	2
		C14	86.98	22.71	1
		C15	70.77	15.88	4
		C16	74.67	17.58	3
Σ		433.08	100		

We note from the Pareto chart, that the most influential reason is insufficient information about the project (C14), Poor contract administration (C13), the contracting type's incompatibility with the project type (C16), and the implementation method is not appropriate

with the project type (C15). These causes are responsible for (70%) of the deviation of the cost of the project so that we must be focus is on the percentage (70%) to solve the problems related to planning reasons.




Figure 6. Showing Secondary planning by Fishbone Diagram




Figure 7. Secondary planning causes by Pareto chart

5.2 Secondary designing causes analysis

The design group (C2) consists of 4 causes arranged in Table 1 and Table 3 showing the

weights and relative importance and the arrangement of each factor in the design group. Figure (8) shows “Fishbone Diagram” and Figure (9) shows “Pareto Chart”.

Table 3: The Weights, Relative Important and ranking for secondary designing causes

Main Causes	Secondary Causes	Weight of secondary causes	Relative important index RI (%)	Ranking
Designing reasons	C21	66.34	15.67	4
	C22	80.34	27.3	2
C2	C23	85.75	36.48	1
	C24	76.65	20.55	3
Σ		309.08	100	

The researcher concluded from the Pareto diagram the mistakes in design documents (C23), design changes (C22), and unrealistic tender cost estimation (C24) are responsible for

(68%) of the deviation of the project cost. so that, focusing on these problems (68%) will lead to solving the problem of cost deviation in the project.




Figure 8. Showing secondary designing causes by Fishbone Diagram




Figure 9. Secondary designing causes by Pareto chart

5.3 Secondary execution causes analysis

The group of reasons for implementation (C3) consists of (11) reasons referred to in Table 1. and Table 4. showing the weights for each

reason and their arrangement within the implementation group. Figure (10) shows “Fishbone Diagram” and the Figure (11) shows “Pareto Chart” to analyze the group of reasons for execution.

Table 4: Weights, relative important and rank for secondary execution causes

Main Causes	Secondary causes	Weight of secondary causes	Relative important index RI (%)	Ranking
Execution reasons C3	C31	70.12	10.78	5
	C32	75.79	12.33	4
	C33	86.75	16.56	2
	C34	88.56	18.55	1
	C35	68.55	9.5	6
	C36	78.45	14.54	3
	C37	55.88	5.23	8
	C38	65.55	8.23	7
	C39	48.23	4.28	9
Σ		637.88	100	

The researcher observed through the Pareto chart that the most influential reason is issues of imported materials and restrictions (C34), failure to agree and conflict management (C33) frequent breakdowns of construction equipment (C36), Changes in orders (C32), Finally, site

incidents and delays due to lack of safety measures (C31) which constitute a percentage (68%) responsible for the deviation of the cost of the project, so that we must focus is on the percentage (68%) to solve the problems related to execution causes.




Figure 10. Showing secondary execution causes by Fishbone Diagram




Figure 11. Secondary execution causes by Pareto chart

5.4 Analysis of main causes

As explained previously, the main causes of cost deviation have been divided into three groups in projects (C1, C2, and C3) with secondary causes in each group. Table 5. Shows each of the average weights, relative importance

and ranking for main causes. From Table 5., we note that the highest average weight is the group of design causes, followed by the group of planning causes, and finally the group of execution causes. Figures (12) and (13) shown “Fishbone Diagram” and “Pareto chart” for main group’s analysis, respectively.

Table 5: Weights, relative importance and rank for Main causes

Main causes groups	Secondary causes	Average weights of main causes	RI%	Rank
Planning Causes C1	C11	72.18	35.66	2
	C12			
	C13			
	C14			
	C15			
Designing Causes C2	C16	77.27	40.22	1
	C21			
	C22			
	C23			
Execution Causes C3	C24	66.47	24.12	3
	C31			
	C32			
	C33			
	C34			
	C35			
	C36			
	C37			
	C38			
C39				
		215.92	100	




Figure 12. Cost deviation causes by Fishbone Diagram

According to the Pareto chart above, the designing causes group (C2) and the planning causes group (C1) are responsible for 80% of the problem. As a result, by focusing on these two

main causes, (80% of the project deviation problem would be solved in the construction projects as shown in Figure (12).




Figure 12. Pareto chart for cost deviation in construction project

6. Using the 5-Why technique

This approach is one of the simplest tools, and it is easy to execute without the use of statistical analysis. The researcher used the 5-Why method to obtain the main causes of cost variance in construction projects and to solve problems. [20]. The number five is chosen at random. The theory goes that if you ask "why" five times, you'll eventually find the root cause. The 5 Why method is often used during the

analysis phase in coordination with other analysis tools such as the Cause-and-Effect Diagram but can be used as a stand-alone tool. Sometimes we can get to the main cause of a problem by means of "3 or 4 Whys". 5 Why is it more effective when the answers are from people who have practical experience in the problem that is being addressed by repeating the question "why" (5), enabling us to reach the root cause of the problem. Figure (13) shown the technique of 5- Whys.




Figure 13. Technique of 5- whys

6.1 Analysis of "5 Whys" for secondary planning causes

Figure (14) shown "5 Whys" analysis for planning causes group. So, we found the root

cause for cost and time deviation in this group among secondary planning reasons according to "5 Whys" analysis is the insufficient information about the project.




Figure 14. 5- Whys analysis for secondary planning causes

6.2 Analysis of “5 Whys” for secondary designing causes

With reference to what has been mentioned previously, Figure (15) showed the analysis of

“4 causes” for designing causes. Therefore, we found the root cause of the deviation in this group among the causes of secondary designing causes according to the "5 Whys" analysis is the unclear owner requirements.




Figure 15. 5- Whys analysis for secondary designing causes

6.2 Analysis of “5 Whys” for secondary execution causes

Figure (16) showed the analysis of “5 whys” for execution causes. Therefore, we found the

root cause of deviation in this group among the causes of secondary execution according to the "5 Whys" analysis is changes in orders.




Figure 16. 5- Whys Analysis for secondary execution causes

Finally, for all secondary (planning, designing, and execution) groups, a 5-Why analysis was performed on the obtained results from the 5-Why analysis. This process is depicted in detail in Figure

(17). According to the final 5-Why analysis, the root cause of the deviation in construction projects is "Owner requirements unclear".




Figure 17. The analysis result of the "5 Whys" for main deviation in project

7. Conclusions

- 1- The root cause identification technique has been used in this study. The goal of this study is to determine the causes of cost deviation in selected case study (Dar Al-nahrain building), across various groups,

such as the planning, design, and execution group. The identification of the root cause of project-related problems is a necessary stage toward cost control and improvement. The researcher depended on the Fishbone Diagram (FD), Pareto Diagram (PD), and

the 5-Why analysis to diagnose these causes in multi-story construction projects

- 2- The study results were defined and diagnosed in general nineteen causes in project under the planning with six causes, designing with four causes and execution groups with nine causes; however, according to Pareto's analysis showed that only ten of the causes were the most important. The major causes concentrated in the designing and planning group.
- 3- The results filtered by using the Five-Whys analysis; This study concludes that the cost deviation in the project was due to insufficient project information, which is the main cause (root cause) for the planning group, while unclear owner requirements are the root cause for the designing group, and changes in orders are the main root cause for the execution group.

References

- [1] F. M. S. Al-Zwainy and I. A.-A. Aidan,(2017). "Forecasting the cost of structure of infrastructure projects utilizing artificial neural network model (highway projects as case study)," *Indian J. Sci. Technol*, vol. 10, no. 20, pp. 1–12,
- [2] F. M. Al-Zwainy and R. Amer, (2016). "Investigation cost deviation of highway project," *Res. J. Appl. Sci. Eng. Technol.*, vol. 13, no. 11, pp. 843–855,.
- [3] I. A. Rahman, A. H. Memon, S. Nagapan, Q. B. A. I. Latif, and A. A. A. Azis, (2012) .Time and cost performance of construction projects in southern and central regions of Peninsular Malaysia," in *IEEE Colloquium on Humanities, Science and Engineering (CHUSER)*, 2012, pp. 52–57.
- [4] M. Kagioglou, R. Cooper, and G. Aouad, (2001).Performance management in construction: a conceptual framework," *Constr. Manag. Econ.*, vol. 19, no. 1, pp. 85–95.
- [5] Y. A. Olawale and M. Sun, "Cost and time control of construction projects: inhibiting factors and mitigating measures in practice," *Constr. Manag. Econ.*, vol. 28, no. 5, pp. 509–526, 2010.
- [6] O. J. Ameh, A. A. Soyingbe, and K. T. Odusami, (2010). Significant factors causing cost overruns in telecommunication projects in Nigeria,.
- [7] F. M. S. Al-Zwainy and R. A. Mezher,(2018.). Diagnose the causes of cost deviation in highway construction projects by using root cause analysis techniques," *Arab. J. Sci. Eng.*, vol. 43, no. 4, pp. 2001–2012.
- [8] V. Sharma, C. H. Caldas, and S. P. Mulva, (2020). Identification and prioritization of factors affecting the overall project cost of healthcare facilities," *J. Constr. Eng. Manag.*, vol. 146, no. 2, p. 4019106.
- [9] M. I. Ahmed and S. E. Rezouki, (2020). Application of Root Causes Analysis Techniques in the Contractor Selection for Highway Projects, *IOP Conf. Ser. Mater. Sci. Eng.*, vol. 901, no. 1,
- [10] L. Muhwezi, J. Acai, and G. Otim, (2014). An assessment of the factors causing delays on building construction projects in Uganda *Int. J. Constr. Eng. Manag.*, vol. 3, no. 1, pp. 13–23.
- [11] F. M. S. Al-Zwainy and T. H. Neran, (2015). Investigation and evaluation of the cost estimation methods of Iraqi communication projects, *Int. J. Eng. Manag. Res. IJEMR*, vol. 5, no. 6, pp. 41–48.
- [12] N. A. Jasim,(2021). Diagnosing the Causes of Poor Quality Management in Iraqi Construction Projects Using Technique of Root Cause Analysis," in *IOP Conference Series: Materials Science and Engineering*, vol. 1076, no. 1, p. 12116.
- [13] F. Al-Zwainy, I. A. Mohammed, and I. F. Varouqa, (2018). Diagnosing the causes of failure in the construction sector using root cause analysis technique, *J. Eng.*
- [14] D. Mahto and A. Kumar,(2008). Application of root cause analysis in improvement of product quality and productivity, *J. Ind. Eng. Manag.*, vol. 1, no. 2, pp. 16–53.
- [15] P. Promsorn, P. Soponsakulrat, C. Adulyanukosol, P. Kaiyarit, and T. Chinda, (2015). Identifying Root Causes of Construction Accidents: Non–Human Error Factors, *J. Commun. Instrum.*, vol. 2, no. 1, p. 4.
- [16] P. M. Williams, (2001). Techniques for root cause analysis," in *Baylor University Medical Center Proceedings*, vol. 14, no. 2, pp. 154–157.
- [17] G. Vorley, (2008). Mini guide to root cause analysis, *London, UK Qual. Manag. Train. Ltd.*
- [18] W. F. Messier, S. M. Glover, and D. F. Prawitt, *Auditing & assurance services* (2008). *A systematic approach*. McGraw-Hill Irwin Boston, MA,
- [19] G. D. Oberlender, (2014). *Project management for engineering and construction*. McGraw-Hill Education,.